

BRUHAT BANGALORE MAHANAGAR PALIKE

Project Division, Yelahanka Zone

SCHEDULE - B**Construction of Sculptures in Parks, Lakes, Circles and Junctions in ward No.01, 02, 03 and 04 of Yelahanka Sub Division**

SNo	Quantity	Item Name	Unit	Approved Rates of Sri. N Purushotham Raju (NPR Infra)	
				In figures	In words
1	1.00	Providing, Fabricating and Fixing of Antique Kannada Alphabets made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each alphabet, appearance and dimensions of each alphabet is as indicated in technical drawings enclosed including cost of all materials, labour, HOM of machinery, Finishing with Spray Painting and providing the support Stand using L-section and centrally fitted with bolt height of 7" complete and Fixing of out-door LED Strip Lighting for through out the periphery and inside all proposed alphabets as per direction of Engineer in Charge. (inclusive of all taxes) As per approved quotation	No	106918.60	Rupees One Lakh(s) Six Thousand Nine Hundred Eighteen And Paise Sixty Only
2	1.00	Providing and fixing of ornamental grill for Hand railing outer frame made out of MS of 50X50X4.5 mm Square Hollow section, inside frame designs made out of 10mm thick Hexagonal Hollow Section height 1.20m, appearance and dimension of hand railing is indicated in drawings including cost of labour etc, complete Fixing of out-door LED Strip Lighting for through out the periphery and inside all proposed alphabets as per direction of Engineer in charge (inclusive of all taxes). Ornamental grill for Hand Railing, As per approved quotation	No	108393.20	Rupees One Lakh(s) Eight Thousand Three Hundred Ninety Three And Paise Twenty Only
3	1.00	Providing, Fabricating and Fixing of Bullock Cart made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each alphabet, appearance and dimensions of each alphabet is as indicated in technical drawings enclosed including cost of all materials, labour, HOM of machinery, Finishing with Spray Painting and providing the support Stand using L-section and centrally fitted with bolt height of 7" complete Fixing of out-door LED Strip Lighting for through out the periphery and inside all proposed alphabets as per direction of Engineer in Charge. Antique Ornamental Sculptures. (inclusive of all taxes) As per approved quotation	No	103535.10	Rupees One Lakh(s) Three Thousand Five Hundred Thirty Five And Paise Ten Only
4	1.00	Providing, Fabricating and Fixing of Antique Kannada Alphabets made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each alphabet, appearance and dimensions of each alphabet is as indicated in technical drawings enclosed including cost of all materials, labour, HOM of machinery, Finishing with Spray Painting and providing the support Stand using L-section and centrally fitted with bolt height of 7" complete Fixing of out-door LED Strip Lighting for through out the periphery and inside all proposed alphabets as per direction of Engineer in Charge. (inclusive of all taxes) As per approved quotation	No	105605.60	Rupees One Lakh(s) Five Thousand Six Hundred Five And Paise Sixty Only

for NPR INFRA TECH

Contractor **Proprietor**

1

[Signature]
 Executive Engineer
 Project Division
 Yelahanka Zone
 BBMP, Bangalore-92

No	Quantity	Item Name	Unit	Approved Rates of Sri. N Purushotham Raju (NPR Infra)	
				In figures	In words
5	1.00	Poviding, Fabricating and Fixing of Antique Kannada Alphabets made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each alphabet, appreance and dimesions of each alphabet is as indicated in techinal drawings enclosed including cost of all materials, labour, HOMof machinery, Finishing with Spray Painting and providing the support Stand using L-section and cetrally fitted with bolt height of 7" complete as per direction of Engineer in Charge. (inclusive of all taxes) As per approved quotation .	No	102222.10	Rupees One Lakh(s) Two Thousand Two Hundred Twenty Two And Paise Ten Only
6	1.00	Poviding, Fabricating and Fixing of Antique Kannada Alphabets made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each alphabet, appreance and dimesions of each alphabet is as indicated in techinal drawings enclosed including cost of all materials, labour, HOMof machinery, Finishing with Spray Painting and providing the support Stand using L-section and cetrally fitted with bolt height of 7" complete as per direction of Engineer in Charge , as per approved quotation	No	151479.80	Rupees One Lakh(s) Fifty One Thousand Four Hundred Seventy Nine And Paise Eighty Only
7	1.00	Poviding, Fabricating and Fixing of Antique Kannada Alphabets made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each alphabet, appreance and dimesions of each alphabet is as indicated in techinal drawings enclosed including cost of all materials, labour, HOMof machinery, Finishing with Spray Painting and providing the support Stand using L-section and cetrally fitted with bolt height of 7" complete Fixeing of out-door LED Strip Lighting for through out the peripery and inside all proposed alphabets as per direction of Engineer in Charge. (inclusive of all taxes)	No	147348.90	Rupees One Lakh(s) Forty Seven Thousand Three Hundred Forty Eight And Paise Ninety Only
8	1.00	Poviding, Fabricating and Fixing of Antique Kannada Alphabets made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each alphabet, appreance and dimesions of each alphabet is as indicated in techinal drawings enclosed including cost of all materials, labour, HOMof machinery, Finishing with Spray Painting and providing the support Stand using L-section and cetrally fitted with bolt height of 7" complete Fixeing of out-door LED Strip Lighting for through out the peripery and inside all proposed alphabets as per direction of Engineer in Charge. (inclusive of all taxes)	No	102222.10	Rupees One Lakh(s) Two Thousand Two Hundred Twenty Two And Paise Ten Only
9	1.00	Poviding, Fabricating and Fixing of Antique Kannada Alphabets made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each alphabet, appreance and dimesions of each alphabet is as indicated in techinal drawings enclosed including cost of all materials, labour, HOMof machinery, Finishing with Spray Painting and providing the support Stand using L-section and cetrally fitted with bolt height of 7" complete Fixeing of out-door LED Strip Lighting for through out the peripery and inside all proposed alphabets as per direction of Engineer in Charge. (inclusive of all taxes) As per approved quotation	No	104706.70	Rupees One Lakh(s) Four Thousand Seven Hundred Six And Paise Seventy Only

for NPR INFRATECH

N. Purushotham
Contractor
Proprietor

[Signature]
Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

No	Quantity	Item Name	Unit	Approved Rates of Sri. N Purushotham Raju (NPR Infra)	
				In figures	In words
10	1.00	Providing, Fabricating and Fixing of Antique Kannada Alphabets made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each alphabet, appearance and dimensions of each alphabet is as indicated in technical drawings enclosed including cost of all materials, labour, HOM of machinery, Finishing with Spray Painting and providing the support Stand using L-section and centrally fitted with bolt height of 7" complete Fixing of out-door LED Strip Lighting for through out the periphery and inside all proposed alphabets as per direction of Engineer in Charge. (inclusive of all taxes) as per approved quotation	No	110039.50	Rupees One Lakh(s) Ten Thousand Thirty Nine And Paise Fifty Only
11	1.00	Providing, Fabricating and Fixing of Antique Kannada Alphabets made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each alphabet, appearance and dimensions of each alphabet is as indicated in technical drawings enclosed including cost of all materials, labour, HOM of machinery, Finishing with Spray Painting and providing the support Stand using L-section and centrally fitted with bolt height of 7" complete Fixing of out-door LED Strip Lighting for through out the periphery and inside all proposed alphabets as per direction of Engineer in Charge.	No	102171.60	Rupees One Lakh(s) Two Thousand One Hundred Seventy One And Paise Sixty Only
12	1.00	Providing, Fabricating and Fixing of Antique Kannada Alphabets made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each alphabet, appearance and dimensions of each alphabet is as indicated in technical drawings enclosed including cost of all materials, labour, HOM of machinery, Finishing with Spray Painting and providing the support Stand using L-section and centrally fitted with bolt height of 7" complete Fixing of out-door LED Strip Lighting for through out the periphery and inside all proposed alphabets as per direction of Engineer in Charge. (inclusive of all taxes) As per approved quotation	No	109726.40	Rupees One Lakh(s) Nine Thousand Seven Hundred Twenty Six And Paise Forty Only
13	1.00	Providing, Fabricating and Fixing of Antique Kannada Alphabets made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each alphabet, appearance and dimensions of each alphabet is as indicated in technical drawings enclosed including cost of all materials, labour, HOM of machinery, Finishing with Spray Painting and providing the support Stand using L-section and centrally fitted with bolt height of 7" complete Fixing of out-door LED Strip Lighting for through out the periphery and inside all proposed alphabets As per direction of Engineer in Charge. (inclusive of all taxes) As per approved quotation	No	136956.00	Rupees One Lakh(s) Thirty Six Thousand Nine Hundred Fifty Six Only

for NPR INFRA TECH


Proprietor

Contractor


Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Sl. No	Quantity	Item Name	Unit	Approved Rates of Sri. N Purushotham Raju (NPR Infra)	
				In figures	In words
14	1.00	Providing, Fabricating and Fixing of Antique Kannada Alphabets made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each alphabet, appearance and dimensions of each alphabet is as indicated in technical drawings enclosed including cost of all materials, labour, HOM of machinery, Finishing with Spray Painting and providing the support Stand using L-section and centrally fitted with bolt height of 7" complete Fixing of out-door LED Strip Lighting for through out the periphery and inside all proposed alphabets as per direction of Engineer in Charge. (inclusive of all taxes) As per approved quotation	No	167114.60	Rupees One Lakh(s) Sixty Seven Thousand One Hundred Fourteen And Paise Sixty Only
15	1.00	Providing, Fabricating and Fixing of Antique Kannada Alphabets made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each alphabet, appearance and dimensions of each alphabet is as indicated in technical drawings enclosed including cost of all materials, labour, HOM of machinery, Finishing with Spray Painting and providing the support Stand using L-section and centrally fitted with bolt height of 7" complete Fixing of out-door LED Strip Lighting for through out the periphery and inside all proposed alphabets as per direction of Engineer in Charge. (inclusive of all taxes) (inclusive of all taxes) As per approved quotation	No	143773.50	Rupees One Lakh(s) Forty Three Thousand Seven Hundred Seventy Three And Paise Fifty Only
16	1.00	Providing, Fabricating and Fixing of Antique Kannada Alphabets made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each alphabet, appearance and dimensions of each alphabet is as indicated in technical drawings enclosed including cost of all materials, labour, HOM of machinery, Finishing with Spray Painting and providing the support Stand using L-section and centrally fitted with bolt height of 7" complete Fixing of out-door LED Strip Lighting for through out the periphery and inside all proposed alphabets as per direction of Engineer in Charge. (inclusive of all taxes) As per approved quotation	No	107625.60	Rupees One Lakh(s) Seven Thousand Six Hundred Twenty Five And Paise Sixty Only
17	1.00	Providing, Fabricating and Fixing of Antique Kannada Alphabets made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each alphabet, appearance and dimensions of each alphabet is as indicated in technical drawings enclosed including cost of all materials, labour, HOM of machinery, Finishing with Spray Painting and providing the support Stand using L-section and centrally fitted with bolt height of 7" complete as Fixing of out-door LED Strip Lighting for through out the periphery and inside all proposed alphabets per direction of Engineer in Charge. (inclusive of all taxes) As per approved quotation	No	109080.00	Rupees One Lakh(s) Nine Thousand Eighty Only

for NPR INFRATECH


Proprietor
Contractor


Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Quantity	Item Name	Unit	Approved Rates of Sri. N Purushotham Raju (NPR Infra)		
			In figures	In words	
18	1.00	Poviding, Fabricating and Fixing of Antique Kannada Alphabets made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each alphabet, appreance and dimesions of each alphabet is as indicated in techinal drawings enclosed including cost of all materials, labour, HOMof machinery, Finishing with Spray Painting and providing the support Stand using L-section and cetrally fitted with bolt height of 7" complete Fixeing of out-door LED Strip Lighting for through out the peripery and inside all proposed alphabets as per direction of Engineer in Charge. (inclusive of all taxes) (inclusive of all taxes) As per approved quotation	No	104686.50	Rupees One Lakh(s) Four Thousand Six Hundred Eighty Six And Paise Fifty Only
19	1.00	Poviding, Fabricating and Fixing of Antique Kannada Alphabets made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each alphabet, appreance and dimesions of each alphabet is as indicated in techinal drawings enclosed including cost of all materials, labour, HOMof machinery, Finishing with Spray Painting and providing the support Stand using L-section and cetrally fitted with bolt height of 7" complete Fixeing of out-door LED Strip Lighting for through out the peripery and inside all proposed alphabets as per direction of Engineer in Charge. (inclusive of all taxes) As per approved quotation	No	113948.20	Rupees One Lakh(s) Thirteen Thousand Nine Hundred Forty Eight And Paise Twenty Only
20	1.00	Poviding, Fabricating and Fixing of Antique Kannada Alphabets made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each alphabet, appreance and dimesions of each alphabet is as indicated in techinal drawings enclosed including cost of all materials, labour, HOMof machinery, Finishing with Spray Painting and providing the support Stand using L-section and cetrally fitted with bolt height of 7" complete Fixeing of out-door LED Strip Lighting for through out the peripery and inside all proposed alphabets as per direction of Engineer in Charge. (inclusive of all taxes) As per approved quotation	No	120311.20	Rupees One Lakh(s) Twenty Thousand Three Hundred Eleven And Paise Twenty Only
21	1.00	Poviding, Fabricating and Fixing of Antique Kannada Alphabets made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each alphabet, appreance and dimesions of each alphabet is as indicated in techinal drawings enclosed including cost of all materials, labour, HOMof machinery, Finishing with Spray Painting and providing the support Stand using L-section and cetrally fitted with bolt height of 7" complete Fixeing of out-door LED Strip Lighting for through out the peripery and inside all proposed alphabets as per direction of Engineer in Charge. (inclusive of all taxes) As per approved quotation	No	108433.60	Rupees One Lakh(s) Eight Thousand Four Hundred Thirty Three And Paise Sixty Only

for NPR INFRATECH


Proprietor

Contractor


Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Quantity	Item Name	Unit	Approved Rates of Sri. N Purushotham Raju (NPR Infra)		
			In figures	In words	
22	1.00	Poviding, Fabricating and Fixing of Antique Kannada Alphabets made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each alphabet, appreance and dimesions of each alphabet is as indicated in techinal drawings enclosed including cost of all materials, labour, HOMof machinery, Finishing with Spray Painting and providing the support Stand using L-section and cetrally fitted with bolt height of 7" complete Fixeing of out-door LED Strip Lighting for through out the peripery and inside all proposed alphabets as per direction of Engineer in Charge. (inclusive of all taxes) As per approved quotation	No	108857.80	Rupees One Lakh(s) Eight Thousand Eight Hundred Fifty Seven And Paise Eighty Only
23	1.00	Poviding, Fabricating and Fixing of Antique Kannada Alphabets made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each alphabet, appreance and dimesions of each alphabet is as indicated in techinal drawings enclosed including cost of all materials, labour, HOMof machinery, Finishing with Spray Painting and providing the support Stand using L-section and cetrally fitted with bolt height of 7" complete Fixeing of out-door LED Strip Lighting for through out the peripery and inside all proposed alphabets as per direction of Engineer in Charge. (inclusive of all taxes) As per approved quotation	No	106413.60	Rupees One Lakh(s) Six Thousand Four Hundred Thirteen And Paise Sixty Only
24	1.00	Poviding, Fabricating and Fixing of Antique Kannada Alphabets made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each alphabet, appreance and dimesions of each alphabet is as indicated in techinal drawings enclosed including cost of all materials, labour, HOMof machinery, Finishing with Spray Painting and providing the support Stand using L-section and cetrally fitted with bolt height of 7" complete Fixeing of out-door LED Strip Lighting for through out the peripery and inside all proposed alphabets as per direction of Engineer in Charge. (inclusive of all taxes)	No	139506.25	Rupees One Lakh(s) Thirty Nine Thousand Five Hundred Six And Paise Twenty Five Only
25	1.00	Poviding, Fabricating and Fixing of Antique Kannada Alphabets made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each alphabet, appreance and dimesions of each alphabet is as indicated in techinal drawings enclosed including cost of all materials, labour, HOMof machinery, Finishing with Spray Painting and providing the support Stand using L-section and cetrally fitted with bolt height of 7" complete Fixeing of out-door LED Strip Lighting for through out the peripery and inside all proposed alphabets as per direction of Engineer in Charge. (inclusive of all taxes)	No	114422.90	Rupees One Lakh(s) Fourteen Thousand Four Hundred Twenty Two And Paise Ninety Only

for NPR INFRATECH



Proprietor

Contractor

6



Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Quantity	Item Name	Unit	Approved Rates of Sri. N Purushotham Raju (NPR Infra)		
			In figures	In words	
26	1.00	Poviding, Fabricating and Fixing of Antique Kannada Alphabets made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each alphabet, appreance and dimesions of each alphabet is as indicated in techinal drawings enclosed including cost of all materials, labour, HOMof machinery, Finishing with Spray Painting and providing the support Stand using L-section and cetrally fitted with bolt height of 7" complete Fixeing of out-door LED Strip Lighting for through out the peripery and inside all proposed alphabets as per direction of Engineer in Charge.	No	104656.20	Rupees One Lakh(s) Four Thousand Six Hundred Fifty Six And Paise Twenty Only
27	1.00	Poviding, Fabricating and Fixing of Antique Kannada Alphabets made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each alphabet, appreance and dimesions of each alphabet is as indicated in techinal drawings enclosed including cost of all materials, labour, HOMof machinery, Finishing with Spray Painting and providing the support Stand using L-section and cetrally fitted with bolt height of 7" complete Fixeing of out-door LED Strip Lighting for through out the peripery and inside all proposed alphabets as per direction of Engineer in Charge. (inclusive of all taxes) As per approved quotation	No	103888.60	Rupees One Lakh(s) Three Thousand Eight Hundred Eighty Eight And Paise Sixty Only
28	1.00	Poviding, Fabricating and Fixing of Antique Kannada Alphabets made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each alphabet, appreance and dimesions of each alphabet is as indicated in techinal drawings enclosed including cost of all materials, labour, HOMof machinery, Finishing with Spray Painting and providing the support Stand using L-section and cetrally fitted with bolt height of 7" complete Fixeing of out-door LED Strip Lighting for through out the peripery and inside all proposed alphabets as per direction of Engineer in Charge. (inclusive of all taxes) As per approved quotation	No	109867.80	Rupees One Lakh(s) Nine Thousand Eight Hundred Sixty Seven And Paise Eighty Only
29	1.00	Poviding, Fabricating and Fixing of Antique Kannada Alphabets made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each alphabet, appreance and dimesions of each alphabet is as indicated in techinal drawings enclosed including cost of all materials, labour, HOMof machinery, Finishing with Spray Painting and providing the support Stand using L-section and cetrally fitted with bolt height of 7" complete Fixeing of out-door LED Strip Lighting for through out the peripery and inside all proposed alphabets as per direction of Engineer in Charge. (inclusive of all taxes) As per approved quotation	No	110241.50	Rupees One Lakh(s) Ten Thousand Two Hundred Forty One And Paise Fifty Only

for NPR INFRATECH


Proprietor

Contractor


Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Quantity	Item Name	Unit	Approved Rates of Sri. N Purushotham Raju (NPR Infra)		
			In figures	In words	
30	1.00	Poviding, Fabricating and Fixing of Antique Kannada Alphabets made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each alphabet, appreance and dimesions of each alphabet is as indicated in techinal drawings enclosed including cost of all materials, labour, HOMof machinery, Finishing with Spray Painting and providing the support Stand using L-section and cetrally fitted with bolt height of 7" complete Fixeing of out-door LED Strip Lighting for through out the peripery and inside all proposed alphabets Fixeing of out-door LED Strip Lighting for through out the peripery and inside all proposed alphabets as per direction of Engineer in Charge. (inclusive of all taxes) As per approved quotation	No	110211.20	Rupees One Lakh(s) Ten Thousand Two Hundred Eleven And Paise Twenty Only
31	1.00	Poviding, Fabricating and Fixing of Antique Kannada Alphabets made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each alphabet, appreance and dimesions of each alphabet is as indicated in techinal drawings enclosed including cost of all materials, labour, HOMof machinery, Finishing with Spray Painting and providing the support Stand using L-section and cetrally fitted with bolt height of 7" complete Fixeing of out-door LED Strip Lighting for through out the peripery and inside all proposed alphabets as per direction of Engineer in Charge. (inclusive of all taxes)	No	106029.80	Rupees One Lakh(s) Six Thousand Twenty Nine And Paise Eighty Only
32	1.00	Poviding, Fabricating and Fixing of Antique Kannada Alphabets made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each alphabet, appreance and dimesions of each alphabet is as indicated in techinal drawings enclosed including cost of all materials, labour, HOMof machinery, Finishing with Spray Painting and providing the support Stand using L-section and cetrally fitted with bolt height of 7" complete Fixeing of out-door LED Strip Lighting for through out the peripery and inside all proposed alphabets as per direction of Engineer in Charge. (inclusive of all taxes)	No	112756.40	Rupees One Lakh(s) Twelve Thousand Seven Hundred Fifty Six And Paise Forty Only
33	1.00	Poviding, Fabricating and Fixing of Antique Kannada Alphabets made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each alphabet, appreance and dimesions of each alphabet is as indicated in techinal drawings enclosed including cost of all materials, labour, HOMof machinery, Finishing with Spray Painting and providing the support Stand using L-section and cetrally fitted with bolt height of 7" complete Fixeing of out-door LED Strip Lighting for through out the peripery and inside all proposed alphabets as per direction of Engineer in Charge. (inclusive of all taxes) As per approved quotation	No	109312.30	Rupees One Lakh(s) Nine Thousand Three Hundred Twelve And Paise Thirty Only

for NPR INFRATECH


Proprietor

Contractor


Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Quantity	Item Name	Unit	Approved Rates of Sri. N Purushotham Raju (NPR Infra)		
			In figures	In words	
34	1.00	Poviding, Fabricating and Fixing of Antique Kannada Alphabets made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each alphabet, appreance and dimesions of each alphabet is as indicated in techinal drawings enclosed including cost of all materials, labour, HOMof machinery, Finishing with Spray Painting and providing the support Stand using L-section and cetrally fitted with bolt height of 7" complete Fixeing of out-door LED Strip Lighting for through out the peripery and inside all proposed alphabets as per direction of Engineer in Charge. (inclusive of all taxes)	No	110342.50	Rupees One Lakh(s) Ten Thousand Three Hundred Forty Two And Paise Fifty Only
35	1.00	Poviding, Fabricating and Fixing of Antique Kannada Alphabets made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each alphabet, appreance and dimesions of each alphabet is as indicated in techinal drawings enclosed including cost of all materials, labour, HOMof machinery, Finishing with Spray Painting and providing the support Stand using L-section and cetrally fitted with bolt height of 7" complete Fixeing of out-door LED Strip Lighting for through out the peripery and inside all proposed alphabets as per direction of Engineer in Charge. (inclusive of all taxes)	No	103848.20	Rupees One Lakh(s) Three Thousand Eight Hundred Forty Eight And Paise Twenty Only
36	1.00	Poviding, Fabricating and Fixing of Antique Kannada Alphabets made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each alphabet, appreance and dimesions of each alphabet is as indicated in techinal drawings enclosed including cost of all materials, labour, HOMof machinery, Finishing with Spray Painting and providing the support Stand using L-section and cetrally fitted with bolt height of 7" complete Fixeing of out-door LED Strip Lighting for through out the peripery and inside all proposed alphabets as per direction of Engineer in Charge. (inclusive of all taxes) As per approved quotation	No	112897.80	Rupees One Lakh(s) Twelve Thousand Eight Hundred Ninety Seven And Paise Eighty Only
37	1.00	Poviding, Fabricating and Fixing of Antique Kannada Alphabets made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each alphabet, appreance and dimesions of each alphabet is as indicated in techinal drawings enclosed including cost of all materials, labour, HOMof machinery, Finishing with Spray Painting and providing the support Stand using L-section and cetrally fitted with bolt height of 7" complete Fixeing of out-door LED Strip Lighting for through out the peripery and inside all proposed alphabets as per direction of Engineer in Charge. (inclusive of all taxes) As per approved quotation	No	114675.40	Rupees One Lakh(s) Fourteen Thousand Six Hundred Seventy Five And Paise Forty Only

for NPR INFRATECH

N. Purushotham
Proprietor
Contractor

[Signature]
Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Quantity	Item Name	Unit	Approved Rates of Sri. N Purushotham Raju (NPR Infra)		
			In figures	In words	
38	1.00	Poviding, Fabricating and Fixing of Antique Kannada Alphabets made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each alphabet, appreance and dimesions of each alphabet is as indicated in techinal drawings enclosed including cost of all materials, labour, HOMof machinery, Finishing with Spray Painting and providing the support Stand using L-section and cetrally fitted with bolt height of 7" complete as per direction of Engineer in Charge.	No	106282.30	Rupees One Lakh(s) Six Thousand Two Hundred Eighty Two And Paise Thirty Only
39	1.00	Poviding, Fabricating and Fixing of Antique Kannada Alphabets made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each alphabet, appreance and dimesions of each alphabet is as indicated in techinal drawings enclosed including cost of all materials, labour, HOMof machinery, Finishing with Spray Painting and providing the support Stand using L-section and cetrally fitted with bolt height of 7" complete Fixeing of out-door LED Strip Lighting for through out the peripery and inside all proposed alphabets as per direction of Engineer in Charge. (inclusive of all taxes) As per approved quotation	No	111453.50	Rupees One Lakh(s) Eleven Thousand Four Hundred Fifty Three And Paise Fifty Only
40	1.00	Poviding, Fabricating and Fixing of Antique Kannada Alphabets made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each alphabet, appreance and dimesions of each alphabet is as indicated in techinal drawings enclosed including cost of all materials, labour, HOMof machinery, Finishing with Spray Painting and providing the support Stand using L-section and cetrally fitted with bolt height of 7" complete Fixeing of out-door LED Strip Lighting for through out the peripery and inside all proposed alphabets as per direction of Engineer in Charge. (inclusive of all taxes) As per approved quotation	No	122997.80	Rupees One Lakh(s) Twenty Two Thousand Nine Hundred Ninety Seven And Paise Eighty Only
41	1.00	Poviding, Fabricating and Fixing of Antique Kannada Alphabets made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each alphabet, appreance and dimesions of each alphabet is as indicated in techinal drawings enclosed including cost of all materials, labour, HOMof machinery, Finishing with Spray Painting and providing the support Stand using L-section and cetrally fitted with bolt height of 7" complete as per direction of Engineer in Charge. (inclusive of all taxes) As per approved quotation	No	124442.10	Rupees One Lakh(s) Twenty Four Thousand Four Hundred Forty Two And Paise Ten Only

for NPR INFRATECH


Proprietor

Contractor

10


Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Quantity	Item Name	Unit	Approved Rates of Sri. N Purushotham Raju (NPR Infra)		
			In figures	In words	
42	1.00	Poviding, Fabricating and Fixing of Antique Kannada Alphabets made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each alphabet, appreance and dimesions of each alphabet is as indicated in techinal drawings enclosed including cost of all materials, labour, HOMof machinery, Finishing with Spray Painting and providing the support Stand using L-section and cetrally fitted with bolt height of 7" complete Fixeing of out-door LED Strip Lighting for through out the peripery and inside all proposed alphabets as per direction of Engineer in Charge. (inclusive of all taxes) As per approved quotation	No	103494.70	Rupees One Lakh(s) Three Thousand Four Hundred Ninety Four And Paise Seventy Only
43	1.00	Poviding, Fabricating and Fixing of Antique Kannada Alphabets made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each alphabet, appreance and dimesions of each alphabet is as indicated in techinal drawings enclosed including cost of all materials, labour, HOMof machinery, Finishing with Spray Painting and providing the support Stand using L-section and cetrally fitted with bolt height of 7" complete Fixeing of out-door LED Strip Lighting for through out the peripery and inside all proposed alphabets as per direction of Engineer in Charge. (inclusive of all taxes) (inclusive of all taxes) As per approved quotation	No	103141.20	Rupees One Lakh(s) Three Thousand One Hundred Forty One And Paise Twenty Only
44	1.00	Poviding, Fabricating and Fixing of Antique Kannada Alphabets made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each alphabet, appreance and dimesions of each alphabet is as indicated in techinal drawings enclosed including cost of all materials, labour, HOMof machinery, Finishing with Spray Painting and providing the support Stand using L-section and cetrally fitted with bolt height of 7" complete as per direction of Engineer in Charge. (inclusive of all taxes)	No	108802.25	Rupees One Lakh(s) Eight Thousand Eight Hundred Two And Paise Twenty Five Only
45	1.00	Poviding, Fabricating and Fixing of Antique Kannada Alphabets made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each alphabet, appreance and dimesions of each alphabet is as indicated in techinal drawings enclosed including cost of all materials, labour, HOMof machinery, Finishing with Spray Painting and providing the support Stand using L-section and cetrally fitted with bolt height of 7" complete as per direction of Engineer in Charge. (inclusive of all taxes)	No	120432.40	Rupees One Lakh(s) Twenty Thousand Four Hundred Thirty Two And Paise Forty Only
46	1.00	Poviding, Fabricating and Fixing of Antique Kannada Alphabets made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each alphabet, appreance and dimesions of each alphabet is as indicated in techinal drawings enclosed including cost of all materials, labour, HOMof machinery, Finishing with Spray Painting and providing the support Stand using L-section and cetrally fitted with bolt height of 7" complete as per direction of Engineer in Charge. (inclusive of all taxes) As per approved quotation	No	104454.20	Rupees One Lakh(s) Four Thousand Four Hundred Fifty Four And Paise Twenty Only

for NPR INFRATECH

Contractor

Proprietor

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Quantity	Item Name	Unit	Approved Rates of Sri. N Purushotham Raju (NPR Infra)		
			In figures	In words	
47	1.00	Poviding, Fabricating and Fixing of Antique Kannada Alphabets made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each alphabet, appreance and dimesions of each alphabet is as indicated in techinal drawings enclosed including cost of all materials, labour, HOMof machinery, Finishing with Spray Painting and providing the support Stand using L-section and cetrally fitted with bolt height of 7" complete Fixeing of out-door LED Strip Lighting for through out the peripery and inside all proposed alphabets as per direction of Engineer in Charge. (inclusive of all taxes)	No	107605.40	Rupees One Lakh(s) Seven Thousand Six Hundred Five And Paise Forty Only
48	1.00	Poviding, Fabricating and Fixing of Antique Kannada Alphabets made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each alphabet, appreance and dimesions of each alphabet is as indicated in techinal drawings enclosed including cost of all materials, labour, HOMof machinery, Finishing with Spray Painting and providing the support Stand using L-section and cetrally fitted with bolt height of 7" complete as per direction of Engineer in Charge. (inclusive of all taxes) As per approved quotation	No	107565.00	Rupees One Lakh(s) Seven Thousand Five Hundred Sixty Five Only
49	1.00	Poviding, Fabricating and Fixing of Antique Kannada Alphabets made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each alphabet, appreance and dimesions of each alphabet is as indicated in techinal drawings enclosed including cost of all materials, labour, HOMof machinery, Finishing with Spray Painting and providing the support Stand using L-section and cetrally fitted with bolt height of 7" complete Fixeing of out-door LED Strip Lighting for through out the peripery and inside all proposed alphabets as per direction of Engineer in Charge. (inclusive of all taxes) As per approved quotation	No	108756.80	Rupees One Lakh(s) Eight Thousand Seven Hundred Fifty Six And Paise Eighty Only
50	1.00	Poviding, Fabricating and Fixing of Antique Kannada Numbers made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each Numbers, appreance and dimesions of each alphabet is as indicated in techinal drawings enclosed including cost of all materials, labour, HOMof machinery, Finishing with Spray Painting and providing the support Stand using L-section and cetrally fitted with bolt height of 7" complete and Fixeing of out-door LED Strip Lighting for through out the peripery and inside all proposed Numbers as per direction of Engineer in Charge. (inclusive of all taxes) As per approved quotation	No	74376.40	Rupees Seventy Four Thousand Three Hundred Seventy Six And Paise Forty Only

for NPR INFRATECH

N- p m f
Proprietor

Contractor


As Engineer
Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Quantity	Item Name	Unit	Approved Rates of Sri. N Purushotham Raju (NPR Infra)	
			In figures	In words
51	1.00	No	82719.00	Rupees Eighty Two Thousand Seven Hundred Nineteen Only
52	1.00	No	84324.90	Rupees Eighty Four Thousand Three Hundred Twenty Four And Paise Ninety Only
53	1.00	No	86506.50	Rupees Eighty Six Thousand Five Hundred Six And Paise Fifty Only
54	1.00	No	96737.80	Rupees Ninety Six Thousand Seven Hundred Thirty Seven And Paise Eighty Only

for NPR INFRATECH


Proprietor

Contractor


Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Quantity	Item Name	Unit	Approved Rates of Sri. N Purushotham Raju (NPR Infra)	
			In figures	In words
55	1.00	No	86415.60	Rupees Eighty Six Thousand Four Hundred Fifteen And Paise Sixty Only
56	1.00	No	85607.60	Rupees Eighty Five Thousand Six Hundred Seven And Paise Sixty Only
57	1.00	No	85122.80	Rupees Eighty Five Thousand One Hundred Twenty Two And Paise Eighty Only
58	1.00	No	84991.50	Rupees Eighty Four Thousand Nine Hundred Ninety One And Paise Fifty Only

for NPR INFRATECH

[Signature]
Proprietor

Contractor

[Signature]
Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Quantity	Item Name	Unit	Approved Rates of Sri. N Purushotham Raju (NPR Infra)		
			In figures	In words	
59	1.00	Poviding, Fabricating and Fixing of Antique Kannada Numbers made out of Brass Casting and other Cast iron and also Mild steel materials as per drawings for each Numbers, appreance and dimesions of each alphabet is as indicated in techinal drawings enclosed including cost of all materials, labour, HOMof machinery, Finishing with Spray Painting and providing the support Stand using L-section and cetrally fitted with bolt height of 7" complete nd Fixeing of out-door LED Strip Lighting for through out the peripery and inside all proposed Numbers as per direction of Engineer in Charge. (inclusive of all taxes) As per approved quotation	No	76396.40	Rupees Seventy Six Thousand Three Hundred Ninety Six And Paise Forty Only
60	8000.00	Providing and fixing of ornamental grill for, inside frame designs made out of 10 mm thick Hexagonal Hollow Section height 1.20m , appearance and dimeson of hand railing is indiacted in drawings including cost of labour etc, complete as per direction of Enginner in charge (inclusive of all taxes). including outdoor duco panting (inclusive of all taxes) As per approved quotation	No	30.30	Rupees Thirty And Paise Thirty Only
61	120.00	Providing and Fixing the I Section ISMB 200 mm X 100 mm X 5.7 mm to support (inclusive of all taxes) (inclusive of all taxes) As per approved quotation	Rmtr	2525.00	Rupees Two Thousand Five Hundred Twenty Five Only
62	1.00	Poviding, Fabricating and Fixing of Bull made out of welded iron link chain materials as per drawings for appreance and dimesions is as indicated in techinal drawings enclosed including cost of all materials, labour, HOMof machinery, complete as per direction of Engineer in Charge. Dimesions :(106 inch X 32 inchesX 60 inches wieght: 1 ton (inclusive of all taxes) As per approved quotation	No	1212000.00	Rupees Twelve Lakh(s) Twelve Thousand Only
63	1.00	Poviding, Fabricating and Fixing of CAR made out of Welded Iron Automobile Parts, materials as per drawings for appreance and dimesions is as indicated in techinal drawings enclosed including cost of all materials, labour, HOMof machinery, complete as per direction of Engineer in Charge. (inclusive of all taxes) Dimesions :108 x 120 x 33 inches Base size required :(12 x 5 feet) wieght: 1.5 Ton approximately (inclusive of all taxes) As per approved quotation	No	1414000.00	Rupees Fourteen Lakh(s) Fourteen Thousand Only
64	1.00	Poviding, Fabricating and Fixing of DEER made out of Welded Iron Automobile Parts, materials as per drawings for appreance and dimesions is as indicated in techinal drawings enclosed including cost of all materials, labour, HOMof machinery, complete as per direction of Engineer in Charge. (inclusive of all taxes) Dimesions : 64 x 102 x 44 inches Base size required: (10.5 x 6 feet) wieght: 1.5 Ton approximately (inclusive of all taxes) As per approved quotation	No	1212000.00	Rupees Twelve Lakh(s) Twelve Thousand Only

for NPR INFRATECH

N. Pravin
Proprietor
Contractor

S. Srinivas
Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Quantity	Item Name	Unit	Approved Rates of Sri. N Purushotham Raju (NPR Infra)	
			In figures	In words
65	1.00	No	1868500.00	Rupees Eighteen Lakh(s) Sixty Eight Thousand Five Hundred Only
	Poviding, Fabricating and Fixing of ASHOKA PILLAR made out of Welded Iron Automobile Parts, materials as per drawings for appreance and dimesions is as indicated in techinal drawings enclosed including cost of all materials, labour, HOMof machinery, complete as per direction of Engineer in Charge. (inclusive of all taxes) Dimesions : 64 x 102 x 44 inches Base size required: (10.5 x 6 feet) wieght: 1.5 Ton approximately (inclusive of all taxes) As per approved quotation			
66	340.72	Cum	266.58	Rupees Two Hundred Sixty Six And Paise Fifty Eight Only
	KSRB 2-1.1 : Earthwork in surface excavation in ordinary soil for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface levelled and neatly dressed, disposed earth to be levelled after breaking of clods and neatly dressed as per specifications. specification. No. KBS 2 1(a) / 2.3.1 Note :Adopt item 2.24 for excavation in all types of soils for lowering & levelling the ground for building works by mechanical means KBS Pg No 6, Item No 2 1			
67	63.17	Cum	129.58	Rupees One Hundred Twenty Nine And Paise Fifty Eight Only
	KSRB 2-11 : Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by Ramming after watering with lead upto 50m. and lift upto 1.5 m. including cost of all labour complete as per specifications..(P-7 Sl.no -2.11) PWD SR 2018-19			
68	53.35	Cum	2600.49	Rupees Two Thousand Six Hundred And Paise Forty Nine Only
	KSRB 2.8 : Providing and Filling in foundation with granite / trap broken metal 100 mm. and down size, with approved sand including hand packing, ramming, watering, including cost of all materials and labour with all lead and lift. complete as per specifications. Specification No. KBS Pg No 7, Item No 2.15			
69	127.41	Cum	5462.20	Rupees Five Thousand Four Hundred Sixty Two And Paise Twenty Only
	KSRB 4-1.3 : Providing and laying in position plain cement concrete of mix 1:4:8(M7.5)with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggretes @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications.Specification No. KBS 4.1, 4.2 Pg No.13 Item No 4.3			

for NPR INFRATECH


Proprietor

Contractor


Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Quantity	Item Name	Unit	Approved Rates of Sri. N Purushotham Raju (NPR Infra)	
			In figures	In words
70	256.88	Cum	6058.53	Rupees Six Thousand Fifty Eight And Paise Fifty Three Only
	KSRB 4.2.2 : Providing and laying in position reinforced cement concrete of Design mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @ 0.460 cum, with super plasticisers @ 3 liters confirming to IS 9103-1999 reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation for footings, pedestals, retaining walls, return walls, walls (any thickness) including attached pilasters, columnspillars, posts, struts, buttresses, bed blocks, anchor blocks & plinths etc., including cost of all materials, labour, HOM of machinery, curing, complete but excluding cost of reinforcement as per specifications. Specification No. KBS 4.1, 4.6, Pg No. 14 Item No. 4.11			
71	15.86	Cum	75976.24	Rupees Seventy Five Thousand Nine Hundred Seventy Six And Paise Twenty Four Only
	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 - Pg No. 18 TMT bars Fe 500			
72	449.86	Cum	488.19	Rupees Four Hundred Eighty Eight And Paise Nineteen Only
	KSRB 4-6.5 : Providing and removing centering, shuttering, strutting, propping etc., for columns, pillars, post and struts, square / rectangular/ polygon in plan including cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2 Pg No. 16 Item No. 4.46.2			
73	12.60	Cum	215.23	Rupees Two Hundred Fifteen And Paise Twenty Three Only
	KSRB 2.3 : Filling available excavated earth (excluding rock) in sides of foundations upto plinth in layers not exceeding 20 cms. in depth, compacting each deposited layer by ramming after watering with lead upto 50 m. and lift upto 1.5 m. including cost of all labour complete as per specifications. Specification. No. KBS 2.9, Pg No.7, Item No 2.10			
74	300.00	Rmtr	151.50	Rupees One Hundred Fifty One And Paise Fifty Only
	Supplying and fixing of 1.1 KV LT UG cable XLPE or Heat resistant PVC insulated, PVC extruded Inner sheath armoured UG LT cable as per IS-1554 (Part-1) or IS-7093 Part-1, Armouring strip thickness in average +5% and resistivity 14 Ohms/Kms (Max) as per IS-3975, 4 core 16 sqmm Iteam rate Iteam rate (PWD electrical S.R material list page: XVIII SL/NO 522)			
75	300.00	Rmtr	83.83	Rupees Eighty Three And Paise Eighty Three Only
	Supplying heavy gauge PVC conduit pipe 20/25/32 mm dia 2mm thick confirming to IS 2509 with suitable size bends metal/pvc junction boxes, adhesive paste etc, and running before concreting and slab. The conduit should be tied to the reinforcement rods by using binding wires and unused ways of junction boxes and pipe ends should be covered using PVC end enclosures, run with 18SWG GI fish wire wherever necessary.			

for NPR INFRA TECH

N - P - M - 4
Contractor Proprietor

Executive Engineer
Project Division
Yeshwanthpur
BBMP, Bangalore-92

Quantity	Item Name	Unit	Approved Rates of Sri. N Purushotham Raju (NPR Infra)		
			In figures	In words	
76	20.00	Supply of LED floodlight luminaire with pressure die cast aluminium housing body for optimal thermal dissipation.Lamp compartment comprising of anti glare clear diffuser with Injection moulded polycarbonate/clear glass material, delivering superior light output. Rated life Burning Hrs 50000 hr @ Lumen Maintenance of 70%, CCT > 5500K, IP 66 optical and electrical compartment & impact resistance of complete luminaire > IK08. Power Factor >0.9 with mains, Surge Protection- Min 5KV along with Over voltage/Overload, short circuit/ miss-wiring protection. Compatible for pole mounting with outer dia of 40mm to 50 mm.Universal Voltage driver to operate wide voltage range from 100V to 270V 50/60Hz application. Compliance to IS10322/ IEC 60598, LM 79 & LM 80 Adherence with RoHS. UL approved MCPCB. Top access street light with single screw to ensure ease of maintenance at the sight site location with minimized minimal tools. LED Light fixture with W System Power consumption. LED Efficiency>130lm/w, nominal CRI >75. Luminaire manufacturer should have inhouse facility accredited by NABL/CPRI & any Government certified agency & Design & Development facility certified by ISO 9001:2008 . Housing with supplier word mark /name shall be Engraved / Embossing on the die cast housing/ Body part.	Rmtr	8888.00	Rupees Eight Thousand Eight Hundred Eighty Eight Only
77	10.00	Supplying and fixing of Group A, regular MCB distribution boards on wall/woodboard/flush mounting using required clamps, bolts, nuts etc., with provision for fixing suitable type capacity MCB'S single phase/ 3 phase / single door with powder coated painting made out of SWG MS enclosure	Rmtr	1222.10	Rupees One Thousand Two Hundred Twenty Two And Paise Ten Only
78	20.00	Supply and fixing miniature circuit breakers on the existing MCB distribution boards using necessary fixing materials and "C" type curve, Indicator ON/OFF energy cross 3 with as required confirming to IEC 60898 Item rate As per approved Data rate	Rmtr	918.09	Rupees Nine Hundred Eighteen And Paise Nine Only
79	7.00	Providing Antique decorative cast iron Electrical Pole Fabricating, supplying and erection of 7 Mtrs long hot dip IS 2062 for base plate with door opening arrangements, including suitable boards, Bakelite sheet and MCBs as per IS specifications suitable to withstand the wind speed of 47 m/sec for Mtrs pole in single section and single joint welded as per IS 9595/IS 10178 AWS having dimensions bottom 350 mm, top 250 mm with 3mm thick, suitable base plate and 4 Nos of long J bolts along with template and the pole shall be hot dip galvanized in single dipping with not less than 65micron as per ASTM-A123 and 153 etc., (excluding foundation) as per drawing appended as per the architectural Drawing and specification as per the directions of Engineer in Charge..... Item rate As per approved Data rate	Rmtr	157560.00	Rupees One Lakh(s) Fifty Seven Thousand Five Hundred Sixty Only
80	100.00	Providing and fixing of LED 30W lighting is indicated in drawings including cost of labour etc, complete as per direction of Engineer in charge (inclusive of all taxes). Ornamental grill for Hand Railing : PWD electrical S.R item no-12.8.2 page no-67	Rmtr	3393.60	Rupees Three Thousand Three Hundred Ninety Three And Paise Sixty Only

for NPR INFRATECH

Contractor

Proprietor

18

Executive Engineer
Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Quantity	Item Name	Unit	Approved Rates of Sri. N Purushotham Raju (NPR Infra)		
			In figures	In words	
81	54.60	Conveying the excavated earth, debries etc., with all lead and lifts including loading and unloading charges etc., complete as per the direction of the Engineer-in-charge. Pg No 136,Item No17.4	Cum	66.51	Rupees Sixty Six And Paise Fifty One Only
82	520.16	14.58. Providing and fixing granite flooring in combination of 19 mm thick (Avg) gang saw water cut LAKARED granite with 86% and with 14% of 19mm thicl (avg) Black granite in CM 1:4 proportion with a coat of rough plastering using CM 1:4, cut to required shape, pattern with paper joints, finished with cement mortar using white cement and colour pigments to match the colour of slab making through jointing with sealant, grooves in joints including cost of curing etc., complete including cost and conveyance of all materials, labour for all items of work, HOM of equipment etc., complete as per specification KBS 14.58 , Pg No 111,Item No 14.58	Cum	3719.26	Rupees Three Thousand Seven Hundred Nineteen And Paise Twenty Six Only
83	522.85	14.55, Providing full nosing for 20 mm thick granite slab using required machinery including cost and conveyance of all materials, labour for all items of work, HOM of equipment etc., complete as per specification KBS No.14.55, Pg No.111	Cum	289.06	Rupees Two Hundred Eighty Nine And Paise Six Only
84	12.42	KSRB 14.4 : Providing and laying flooring and steps fine dressed granite stone slabs 40 mm thick on cement mortar bed 1:6, and pointed with cement mortar 1:3 over existing cement concrete bed , including cost of materials, labour, curing complete as per specifications. Specification No. KBS 14.26 Pg No.103	Cum	3469.71	Rupees Three Thousand Four Hundred Sixty Nine And Paise Seventy One Only
85	431.88	Providing and fixing Stainless steel staircase raling as per Chief Architect Drawing No. 11520/ HRSC with hand rail 50mm dia 16 guage hollow pipe welded to vertical hollow 50 mm dia pipe of 16 guage, stainless steel vertical pipe spaced at 1.20 m regular intervals, and 5 Nos of 25mm dia. Stainless steel hollow horizontal pipe are welded to vertical 50mm dia hollow pipe. The entire assembly is fixed to staircase concrete by using expansion bolts by drilling concrete etc., complete including cost of materials, labour, HOM of machineries and electrical charges, etc., complete as per specifications.. Pg No. 45 Item No. 7.38	Cum	6446.08	Rupees Six Thousand Four Hundred Forty Six And Paise Eight Only
86	108.00	Providing Granite holes of 50 mm dia for fine dressed granite stone slabs 40 mm thick (As per Approved data Rate)	Cum	121.20	Rupees One Hundred Twenty One And Paise Twenty Only
87	6.00	Providing and laying fine dressed granite stone pillar of 300 mm dia nd 2.5 M height including cost of materials, labour, curing complete as per specifications. (As per approved Data rate)	Cum	11110.00	Rupees Eleven Thousand One Hundred Ten Only
88	6.00	Providing and laying fine dressed granite stone pillar of 300 mm dia nd including cost of materials, labour, curing complete as per specifications. (As per approved Data rate)	Cum	5555.00	Rupees Five Thousand Five Hundred Fifty Five Only

for NPR INFRATECH

N. Prasad
Proprietor

Contractor

19

[Signature]
Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Quantity	Item Name	Unit	Approved Rates of Sri. N Purushotham Raju (NPR Infra)	
			In figures	In words
89	29.54	Cum	91.00	Rupees Ninety One Only
	KSRRB M300-2.2. Grassing with Doobs grass KSRRB M300-2.1. Grassing with Doobs grass including watering and maintenance of the lawn for 30 days or more till the grass forms a thick lawn free from weeds and fit for moving including supplying good earth if needed complete as per specifications. MORTH Specification No. 307 ii) In rows 7.5 cm apart in either direction, item No 19.79, Page 148 PWD SR 2018-19			
90	39.65	Cum	5740.54	Rupees Five Thousand Seven Hundred Forty And Paise Fifty Four Only
	KSRB 5.4.3 : Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6 stone Masonary in superstructure with cement mortar , edge of stones chistle dressed in courses not less than 15 cms high, bond stones at two 2M. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.4.3, Pg No 25, Item No 5.12			
91	222.42	Sqm	976.37	Rupees Nine Hundred Seventy Six And Paise Thirty Seven Only
	KSRB 5-14 : Providing and constructing load bearing wall with solid concrete blocks of size 400 X 200X200mm having block density not less than 1800kg/m3 having a minimum average compressive strength 5.00N/mm2 confirming to IS 2185 (part 1) :2005 and constructed with cement mortar 1:4, as per IS 2572:2005 including cost of materials, labour charges, scaffolding, curing, hire charges of machinaries etc., complete as per specifications. KBS No.5.14, Pg No 27 Item No. 5.26.1			
92	943.22	Sqm	2932.37	Rupees Two Thousand Nine Hundred Thirty Two And Paise Thirty Seven Only
	Providing and laying flooring using prepolished, water cut/gang saw 19mm thick granite laid over bed of 20mm thick 1:4 cm & jointed with neat cement slurry mixed with pigment to match shade of granite slabs including laying POP on finished surface and cleaning the surface, including the cost of all materials and labours etc., complete as per specifications. - using silver grey granite / Multy Red / Ruby Red / Black / HassanGreen Granite of width not less than 1200mm Specification No. KBS 14.47.1 Pg No.109			
93	6.79	Cum	7183.12	Rupees Seven Thousand One Hundred Eighty Three And Paise Twelve Only
	KSRB 6-2.3 : Providing and constructing burnt brick masonry with approved quality of non-modular bricks of standard size of class designation 5.0Newton per sqmm (table moulded) with cement mortar 1:6 for basement and superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. Specification No. KBS 6.2, page no.29, item no 6.2 PWD Sr 2018-19			
94	208.98	Sqm	218.40	Rupees Two Hundred Eighteen And Paise Forty Only
	KSRB15-1.6 : Providing rough cement plastering 15mm thick in single coat with cement mortar 1:4, to brick masonry for base of dadoing works with sand of approved quality, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. KBS No 15.1.6, Pg No. 115 Item No. 15.6			

for NPR INFRATECH

N-purush
Contractor Proprietor

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Quantity	Item Name	Unit	Approved Rates of Sri. N Purushotham Raju (NPR Infra)		
			In figures	In words	
95	210.06	KSRB 15-16.1 Providing and applying painting in two coats with plastic emulsion paint of approved brand on wall surface to give an even approved shade after thoroughly brushing the surface, free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications. - with primer item No.15.53.2 Page No. SR 2018-19	Sqm	109.20	Rupees One Hundred Nine And Paise Twenty Only
96	160.00	Supplying heavy gauge PVC conduit pipe 40mm dia 2.5mm thick confirming to IS 2509 with suitable size bends, junction boxes, adhesive paste etc., and fixing using inverted wood plugs in case of RCC ceiling and RCC wall / stone structure or rawl plugs in case of brick walls and cement plastering the damaged portion using heavy gauge saddles at an interval of 700mm using NF screws. item no-3.4,Item 3.4.1,Item 3.4.2 page no-2, PWD SR 2019-20 (40mm,dia.2.5mm thick)	Rmtr	106.05	Rupees One Hundred Six And Paise Five Only
97	44.00	Supply of LED floodlight luminaire with pressure die cast aluminium housing body for optimal thermal dissipation.Lamp compartment comprising of anti glare clear diffuser with Injection moulded polycarbonate/clear glass material, delivering superior light output. Rated life Burning Hrs 50000 hr @ Lumen Maintenance of 70%, CCT > 5500K, IP 66 optical and electrical compartment & impact resistance of complete luminaire > IK08. Power Factor >0.9 with mains, Surge Protection- Min 5KV along with Over voltage/Overload, short circuit/ miss-wiring protection. Compatible for pole mounting with outer dia of 40mm to 50 mm.Universal Voltage driver to operate wide voltage range from 100V to 270V 50/60Hz application. Compliance to IS10322/ IEC 60598, LM 79 & LM 80 Adherence with RoHS. UL approved MCPCB. Top access street light with single screw to ensure ease of maintenance at the sight site location with minimized minimal tools. LED Light fixture with W System Power consumption. LED Efficiency>130lm/w, nominal CRI >75. Luminaire manufacturer should have inhouse facility accredited by NABL/CPRI & any Government certified agency & Design & Development facility certified by ISO	Each	6868.00	Rupees Six Thousand Eight Hundred Sixty Eight Only
98	32.00	Supplying and flush modular powder coated / galvanized metal box suitable for mounting modular switch plates. the box should be firm flush mounted after due groove cutting in brick /stone/C.C wall .. item no-1.2,Item 1.2.2,Item 1.2.3 page no-2, PWD SR 2018-19	Each	106.05	Rupees One Hundred Six And Paise Five Only
99	8.00	Supply and fixing of bakelite D.P /socket/switch with/ without neon indicator over existing wood board or flush mounting in plastic plates/niches as per IS 1293 and IS 3854.,Item 3.6.11 page no-10, PWD SR 2018-19	Each	163.62	Rupees One Hundred Sixty Three And Paise Sixty Two Only
100	8.00	Supplying and fixing of Group A, regular MCB distribution boards on wall/woodboard/flush mounting using required clamps, bolts, nuts etc., with provision for fixing suitable type capacity MCB'S single phase/ 3 phase / single door with powder coated painting made out of SWG MS enclosute. item no-5.18,Item5.18.4 page no-27,28 PWD SR 2018-19.	Each	1222.10	Rupees One Thousand Two Hundred Twenty Two And Paise Ten Only

for NPR INFRA TECH

N-pm.4
Contractor Proprietor

S. N. S.
Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Quantity	Item Name	Unit	Approved Rates of Sri. N Purushotham Raju (NPR Infra)		
			In figures	In words	
101	8.00	Supply and fixing miniature circuit breakers on the existing MCB distribution boards using necessary fixing materials and "C" type curve, Indicator ON/OFF energy cross -3 with as required confirming to IEC 60898 item no-5.17 Item 5.17.4. page no-27, PWD SR 2018-19. ♦	Each	918.09	Rupees Nine Hundred Eighteen And Paise Nine Only
102	200.00	Wiring for lighting/power circuit using ♦ Grade using one of FRLS PVC insulated 1100 volts grade, multistrand copper with ♦ low conductor resistance single core wire ♦ in ♦ open or concealed system of wiring. With specified IS-694: confirming to Latest amendements item no-2.3,Item2.3.4 page no-5,6 PWD SR 2018-19.	Each	45.45	Rupees Forty Five And Paise Forty Five Only
103	8.00	Supplying and fixing regular MCB distribution boards on wall / wood board / flush mounting using required clamps, bolts, nuts etc., with provision for fixing suitable type capacity MCB's single phase / 3 phase / single door with powder coated painting. Made out of 14 SWG MS enclosure.item no-5.18,page no-27, PWD SR 2019-20.	Each	1818.00	Rupees One Thousand Eight Hundred Eighteen Only
104	405.50	Supplying of 1.1 KV LT UG cable XLPE or Heat resistant PVC insulated, PVC extruded Inner sheath armoured UG LT cable as per IS-1554 (Part-1) or IS-7098 Part-1, Armouring strip thickness in average +5% and resistivity 14 Ohms/Kms (Max) as per IS-3975, ♦ item no-6.4.2, page no-40, PWD SR 2019-20.	Rmtr	131.30	Rupees One Hundred Thirty One And Paise Thirty Only
105	360.00	Providing and filling sand in excavated trench to cover already laid UG cable to a depth of 150 mm all-round the cable item 6.7,page no- 41 SR 2018-19. ♦	mtr	101.00	Rupees One Hundred One Only
106	8.00	Supplying and fixing L.T. cast Iron pot heads suitable for 1.1KV class UG cable filled with necessary bitumen/ insulating compound complete with terminals lamps, bolts, nuts and washers etc. item 6 10.5,page no- 42SR 2018-19.	Each	624.18	Rupees Six Hundred Twenty Four And Paise Eighteen Only
107	1.80	KSRB 15-15.1 : Providing and applying painting in two coats with plastic emulsion paint of approved brand on wall surface to give an even approved shade after thoroughly brushing the surface, free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications. - with primer	Sqm	93.12	Rupees Ninety Three And Paise Twelve Only
108	146.00	KSRB 14.6-1: Providing and laying heavy duty cobble stones 60 mm thick interlock pavers, using cement and course sand for manufacture of blocks of approved size, shape and colour with a minimum compressive strength of 281 kg per sqm over 50mm thick sand bed (average thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in between joints, final compaction of paver surface joints into its final level, including cost of materials, labour and HOM of machineries complete as per specifications. Specification No. KBS	Sqm	1127.36	Rupees One Thousand One Hundred Twenty Seven And Paise Thirty Six Only

for NPR INFRATECH

N-purushotham.f

Contractor Proprietor

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Quantity	Item Name	Unit	Approved Rates of Sri. N Purushotham Raju (NPR Infra)		
			In figures	In words	
109	80.00	KSRRB M1200-48.2. Construction of cement concrete kerb with top and bottom width 115 and 165 mm respectively, 250 mm high in M-20 grade PCC on M-10 grade foundation 150 mm thick, foundation having 50 mm projection beyond kerb stone, kerb stone laid with kerb lying machine, foundation concrete laid manually, all complete as per Clause 400.8 complete as per specifications. B. Using Concrete Batching and Mixing Plant MORTH Specification No.408item No 26.127, Page no.217 PWD SR 2018-19	mtr	295.93	Rupees Two Hundred Ninety Five And Paise Ninety Three Only
110	60.00	Providing and laying For elevation using white sadarhalli stone with stone chiesing and fine dressed granite stone slabs 100 mm thick with cement mortar 1:3 including cost of materials, labour, curing complete as per specifications. (AS per Appoved Data rate incluing GST)Elevation Stone for aesthithic purpose @ TOP OF WALL (1X0.3X0.1) granite size	Sqm	4898.50	Rupees Four Thousand Eight Hundred Ninety Eight And Paise Fifty Only
111		GST @ 12% (For SR 2018-19 Items Only)			

for NPR INFRATECH

N - pram4

Proprietor

Contractor

[Signature]
Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92